




DR CONFIDENTIAL
DOCUMENT AND THE DATA DISCLOSED
HEREIN IS NOT TO BE REPRODUCED,
DISCLOSED IN WHOLE OR IN PART
WITHOUT PERMISSION OF VICOR CORP.

REV.	DESCRIPTION	DATE	APPROVED
#1	DRAWN FOR DEVELOPMENT	8/6/01	CF
#2	REVISED PER MARK-UP	03/11/03	CF

查询24252供应商

.025 (#22 AWG) SOLID TINNED LEADS



捷多邦，专业PCB打样工厂，24小时加急出货

MARKING:
1. VENDOR
2. DATE CODE
3. MFD/TOL/VDC

RICAL CHARACTERISTICS @ T=25°C (UNLESS OTHERWISE SPECIFIED)									
PARAMETER	SYMBOL	MIN	TYP	MAX	UNITS	TEST CONDITIONS			
CAPACITANCE	C	243		297	uF	@ 120 Hz, .5 Vrms			
RMS CURRENT	I _{DC}			13	uA	@ V _{DC}			
WVOLTAGE RESISTANCE	ESR		90		mΩ	@ 100 KHz 1VRMS			
DC VOLTAGE	V _{DC}	10			V				
DISSIPATION FACTOR	D			8	%	@ 120 Hz 1VRMS			
OPERATING TEMPERATURE		-55°C TO +125°C				WITH PROPER VOLTAGE DERATING			



DRAWN BY C. C. KEAY		DATE 8/6/01		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES TOLERANCES ARE: FRACTIONS DECIMALS ANGLES +1/64 .XX ± .01 ± 1° .XXX ± .005	
THIRD ANGLE PROJECTION		SIZE B		FSCM NO. 67131	
DO NOT SCALE DRAWING		SCALE 2:1		DWG NO 24252	
				REV #2	
				SHEET 1 OF 1	

CAP, SOLID TANTALUM,
270 uF ± 20%, 10V