




DR CONFIDENTIAL
DOCUMENT AND THE DATA DISCLOSED
HEREIN IS NOT TO BE REPRODUCED,
DISCLOSED IN WHOLE OR IN PART
WITHOUT PERMISSION OF VICOR CORP.

REV.	DESCRIPTION	DATE	APPROVED
#1	DRAWN FOR DEVELOPMENT	8/6/01	CF
#2	REVISED PER MARK-UP	03/11/03	CF

查询24253-2供应商

.025 (#22 AWG) SOLID TINNED LEADS



捷多邦, 专业PCB打样工厂, 24小时加急出货

MARKING:
1. VENDOR
2. DATE CODE
3. MFD/TOL/VDC

TYPICAL CHARACTERISTICS @ T=25°C (UNLESS OTHERWISE SPECIFIED)									
PARAMETER	SYMBOL	MIN	TYP	MAX	UNITS	TEST CONDITIONS			
CAPACITANCE	C	108		132	uF	@ 120 Hz, .5 Vrms			
RISER CURRENT	I _{DCL}			12	uA	@ V _{DCW}			
EQUIVALENT RESISTANCE	ESR		150		mΩ	@ 100 KHz 1VRMS			
DC VOLTAGE	V _{DCW}	20			V				
DIPANG FACTOR	D			6	%	@ 120 Hz 1VRMS			
OPERATING TEMPERATURE		-55°C	T0	+125°C		WITH PROPER VOLTAGE DERATING			



CAP, SOLID TANTALUM,
120 uF ± 20%, 20V

SIZE	FSCM NO.	DWG NO	REV
B	67131	24253	#2
THIRD ANGLE PROJECTION		SCALE	SHEET 1 OF 1
DO NOT SCALE DRAWING		2:1	