




DRG CONFIDENTIAL
ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
EXCEPT WHERE SHOWN OTHERWISE. THIS DOCUMENT IS THE PROPERTY OF VICTOR ELECTRONICS, INC. AND IS NOT TO BE REPRODUCED, COPIED, OR DISCLOSED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF VICTOR ELECTRONICS, INC.

REV.	DESCRIPTION	DATE	APPROVED
#1	DRAWN FOR DEVELOPMENT	8/6/01	CF
#2	REVISED PER MARK-UP	03/11/03	CF

查询24255供应商

.025 (#22 AWG) SOLID TINNED LEADS



捷多邦, 专业PCB打样工厂, 24小时加急出货

MARKING:
1. VENDOR
2. DATE CODE
3. MFD/TOL/VDC

PERICAL CHARACTERISTICS @ T=25°C (UNLESS OTHERWISE SPECIFIED)

PARAMETER	SYMBOL	MIN	TYP	MAX	UNITS	TEST CONDITIONS
CAPACITANCE	C	24.3		29.70	uF	@ 120 Hz, .5 Vrms
DC CURRENT	I _{DC}			8	uA	@ V _{DC}
EQUIVALENT RESISTANCE	ESR		210		mΩ	@ 100 KHz 1VRMS
VOLTAGE	V _{DC}	50			V	
DIPANGTION FACTOR	D			6	%	@ 120 Hz 1VRMS
OPERATING TEMPERATURE		-55°C	T0	+125°C		WITH PROPER VOLTAGE DERATING



CAP, SOLID TANTALUM,
27 uF, +20 % , 50V

SIZE	FSCM NO.	DWG NO	REV
B	67131	24255	#2
SCALE	2:1	SHEET	1 OF 1